



Lower Satsop River Floodplain Project



October 2014






- *Review of project history*
- *Project alternatives*
 - *No Action*
 - *Dikes and spoils removal*
 - *Flood corridor protection*
 - *Channel maintenance*
 - *Bank Protection*
- *Analysis of flood and bank erosion impacts*
- *Next steps to select preferred alternative*
 - *Evaluation criteria*
 - *Stakeholder input & discussion*

Lower Satsop River

Review of project history

- **Local concerns**
 - Loss of farm land & soils
 - Flooding
- **Current project builds off of previous studies**
- **WDFW property**



USACE, 2002-2004

Purpose:

Floodplain Restoration

Proposed Restoration

- Removing all dikes/levees & spoils at pits
- Fill ponds with spoils
- Interconnect ponds
- Enhance or create new egress channel



Rip Rap Removal Project, WSE 2013

Purpose:

Remove left bank hardening to reduce right bank erosion

- Analysis indicated a more comprehensive solution required
 - Rip-Rap removal alone would not offer significant protection for downstream properties
 - Removing rip-rap would increase risk to Keys Rd
 - Firehose analogy – allowing larger degree of freedom makes channel less predictable



Project Scope:


- Lower Satsop River

Funding:

- Chehalis River Basin Flood Authority
- Development of project alternatives & analysis
- Preliminary design (60%)
- June 2015

Goals:

- Protect infrastructure and agricultural
- Create better fish and wildlife habitat
- Flood reduction





Stakeholder Meeting #1

March 2014

What did we talk about:

- *History of project*
- *Channel migration zones & river history*
- *Goals & objectives*
- *Next steps*

What did we hear:

- *Strong local community*
- *Shared experience about flooding and bank erosion*
- *Gravel removal support; frustration about permitting*
- *Bank erosion concerns more than flooding concerns*




Stakeholder Meeting #2

October 2014


Outcome:

- *Review project alternatives*
- *Review analysis of project alternatives*
- *Stakeholder input*
- *Prepare for evaluation of project alternatives*


Pre-European fan extent




Railroad & Highway fan impact




Keys Road fan impact




Cumulative loss to fan surface



Revetments




Hydrologic changes - Flow



Hydrologic changes - Stage

Satsop River USGS - Observed Peak Stages






Project Goals

1. Reduce bank erosion
2. Improve habitat
3. Reduce flooding


Alternatives

- A1 - No Action
- A2 – Spoils & Dike Removal
- A3 – Migration Corridor
- A4 – Channel Maintenance
- A5 – Bank Protection


Alternative A1 – No Action



Alternative A1 – No Action





Alternative A2-A – Spoils & Dikes Regrading



2-Year Water Depth

Existing



A2



Depth Difference – Existing VS A2

2-Year

10-Year






A2-A – Spoils & Dike Regrading

- Goals
 - No immediate erosion benefit
 - Significant habitat benefit
 - Some flood reduction benefit
- Expense
 - Moderate expense
 - Potential for cost sharing?
- Concerns
 - None

Alternative A2-B – Regrading & revetment removal





Approximate
Cost:
\$5,600,000
To
\$9,600,000

Existing Velocity

10,000 CFS

20,000 CFS




A2-B – Spoils, Dike Regrading & Revetment Removal

- Goals
 - No immediate erosion benefit
 - Significant habitat benefit
 - Some flood reduction benefit
- Expense
 - Higher expense
- Concerns
 - Erosion risk at Keys Road
 - Less certainty for downstream landowners

Alternative A3-A – Channel Migration Corridor


Keys Road as boundary



Approximate
Cost:
\$3,700,000


Alternative A3-A – Channel Migration Corridor

Keys Road as boundary



Alternative A3-B – Channel Migration Corridor

Keys Road relocation




Approximate
Cost:
\$13,400,000
to
\$16,700,000

A3 – Corridor Options

- Goals
 - No immediate erosion benefit
 - Long term habitat benefit
 - No flood benefit beyond A2
- Expense
 - Moderate to extremely high expense
- Concerns
 - Only partially addresses financial risk of landowners
 - Ag land still at risk


Alternative A4 – Channel Maintenance

Pilot channel & bar scalping



Approximate
Cost:
\$3,600,000 now
Plus
\$160,000
annually



Concept for Alternative A4 – Pilot Channel & Bar Scalping



Depth Difference - Existing VS A4

2-Year



10-Year



Depth Difference – Existing VS A2

2-Year



10-Year



10,000 CFS Velocity


Existing

A4



Existing VS A4 10,000 CFS Velocity Difference Plot


- Velocity slows at bend near Port well
- Velocity increases in channel upstream of pilot channel, where velocity is already high
- Velocity at bar downstream of pilot channel increases
- Velocity in channel downstream of pilot channel decreases



A4 – Channel Maintenance

- Goals
 - Both erosion reduction and erosion increase
 - Both habitat benefit and habitat loss
 - Small flood benefit beyond A2
- Expense
 - Moderate, with ongoing annual expense
- Concerns
 - Increases erosion in some areas
 - Permitting
 - Long term commitment

Alternative A5 – Bank Protection



Approximate
Cost:
\$7,800,000

Concept for Alternative A5 – Bank Protection - LWD



Concept for Alternative A5 – Bank Protection - Rock



Satsop River Rock Bank Protection - A5

Washington Department of Fish & Wildlife,
Grays Harbor County, WA



110 Prefontaine Pl S, Suite 508
Seattle, WA, 98104
(206) 521-3000

SCALE: 1" = 240'

DATE: XXXX 2014

JOB NO: 14-004


PLATE

7

Example of Bank Protection



Alternative A5 – Bank Protection with Revetment Removal



Approximate
Cost:
\$10,100,000
To
\$13,100,000

A5 – Bank Protection Options

- Goals
 - Significant erosion benefit
 - Both habitat benefit and habitat loss
 - No flood benefit beyond A2
- Cost
 - High to extremely high
- Concerns
 - Limits migration to a smaller than natural corridor
 - Difficult to permit



Summary

A1 – No action

- No benefit, no additional cost

A2 - Spoils/Dikes Regrading

- Lowers peak floods marginally
- Improves habitat

A3 - Corridor

- No additional flood or erosion benefit
- Habitat improvement
- Financial benefit to landowners over A1
- Relatively inexpensive, unless Keys Road moved


A4 – Channel Maintenance

- Some additional flood benefit
- Relatively inexpensive
- Trades erosion risk from one spot to another
- Loss of habitat
- Difficult to permit

A5 – Bank Protection

- No additional flood benefit
- Erosion benefit
- Loss of habitat (floodplain function)
- Constricted migration zone
- High cost

Phase 3 Project Proposal



Lower Satsop Restoration Phase III Elements

Elements include:

- Move spoils piles & dikes to partially fill ponds (approx. 1/3 full) & create safer sideslopes
- Excavate gaps in revetment to reconnect floodplain channels
- Restore & enhance floodplain channels
- Interconnect ponds and restore outlet channel
- Protect Keys Road from overbank/floodplain channel flow
- Revegetate disturbed areas
- Assist with relocation of Port well

Order of Magnitude Cost Estimate:

- Regrade spoils: 160,000 CY \$2,000,000
- Floodplain channels (3,000 feet): 6,000 CY \$150,000
- Revegetation 14 Acres \$250,000
- Keys Road Protection Lump Sum \$200,000
- Port Well Relocation WDFW portion \$500,000
- Final Design & Permitting Lump Sum \$200,000

Total \$3,300,000

Lower Satsop Phase III Elements

Washington Department of Fish & Wildlife,
Grays Harbor County, WA

WATERSHED
SCIENCE & ENGINEERING
110 Prefontaine Pl S, Suite 508
Seattle, WA, 98104
(206) 521-3000

SCALE: 1" = 1,000'
DATE: Sep. 2014
JOB NO: 14-004

PLATE
1



Next Steps

Stakeholder input

- **Today's discussion**
- **Comment form**

Project alternatives evaluation

- **Erosion and flood reduction**
- **Stakeholder support**
- **Ecological benefits**
- **Feasibility**
- **Sustainability**
- **Cost**



Please fill out:

Stakeholder Survey and Comments

Alternative	Score (1 – 4)	Comments
A1-No action		
A2- Dikes and Spoils removed		
A3- Flood Corridor Protection		
A4-Channel Maintenance		
A5-Bank Protection		

1-no support, 2-low support, 3-medium support, 4-high support

Discussion

Stakeholder Meetings

Preliminary Schedule

- Kick-Off
 - March 2014
- Alternative Discussion
 - October 16, 2014
- Preferred Alternative Selected
 - November 2014
- Preliminary Design & Permit Strategy
 - December 2014
- Final Project Design & Report
 - June 2015

Contact Information

Washington Department of Fish and Wildlife



Michelle Cramer

Environmental Engineer

michelle.cramer@dfw.wa.gov

(360) 902-2611

Doris Small

Fish and Wildlife Habitat Biologist

doris.small@dfw.wa.gov

(360) 902-2258

WATERSHED Science & Engineering

web: www.watershedse.com

(206) 521-3000



Mark Indrebo

Larry Karpack

Jeff Johnson

Geomorphologist

Engineer/Geomorphologist

Hydrologist/Engineer

mark@watershedse.com

jeff@watershedse.com

larry@watershedse.com