

# Chehalis Basin Strategy Geomorphology and Sediment Transport

---

*Technical Workshop*  
*May 7, 2014*



# Geomorphology Considerations

- Project operation could affect:
  - Peak flows (sediment transport)
  - Sediment input (reservoir storage, change in bank erosion)
  - Large woody debris input/transport
- Potential Key Geomorphology/Habitat Effects
  - Substrate (spawning gravel, interstitial rearing, etc.)
  - Channel forming processes (meander rate, LWD input, holding pools, etc.)
  - Floodplain and off-channel connectivity


# Effects of 2007 Flood

- Extreme storm/flood event – 500 yr return flow at Doty gage
- Rainfall resulted in more than 1,000 landslides in Chehalis basin (sediment/wood)
  - 5.7 – 8.7 million cubic yards of sediment delivered from slides; deposition in channel/floodplain
  - Over 200 acres of woody debris accumulated in floodplain

# Effects of 2007 Flood


- Gravel-sized material stored upstream of RM 104, currently providing excellent spawning habitat
- Gravel will be gradually transported downstream
  - Substrate will coarsen through time (eventually return to pre-flood conditions, less spawning gravel)
  - Likely take several decades based on bedload transport rates
- Channel avulsion at RM 105

# Geomorphic Reaches and Sub-Reaches






# Substrate Characteristics




# Bedload Transport Modeling

- Used HEC-RAS unsteady flow model to determine shear stress (main channel) for 20 years of existing and with-project flow scenarios
- Used bedload transport calculations to determine daily bedload transport under Flood Retention Only and Multi Purpose scenarios, compared to existing conditions


# Bedload Transport – Existing Conditions




# Balance of Changed Input/Transport – Flood Retention Only




# Balance of Changed Input/Transport – Multi Purpose




# Channel Migration Analysis




# Channel migration – RM 104-105




# Channel migration RM 88-91



# Channel migration RM 82-86



# Channel Migration Rates



# Channel Migration

- Small amounts of channel migration occur during small (2-year recurrence) peak flows  $\sim 10,000$  cfs at Doty
- Major channel change takes place in response to large woody debris loading (e.g., 2007)
- Reduction in peak flows under with-Project scenarios would likely result in narrower active channel and somewhat less channel migration


# Large Woody Debris

- Existing low levels of large woody debris
- Large woody debris would be trapped in either reservoir
- Management plan – likely transport wood around structure, place in downstream channel
- Interruption/reduction of large woody debris transport
- Less input of large woody debris if less bank erosion between dam and RM 70

# Bedload Transport through Reservoir

- Bedload transport would occur if:
  - No pool
  - Discharge high enough to transport bedload
- Multi-purpose – pool at all times, no bedload transport through reservoir, approx. 90% of fine grained sediment retained
- Flood Retention Only – pool only during peak flows; portion of bedload would be transported through structure (50-75%)


# Bedload Transport Through Flood Retention Only Reservoir




# Reservoir Sediment and Debris Loading

- Long term operations/maintenance concern
- Multi-Purpose
  - All bedload, 86-93% of suspended load (42 acre-ft/yr)
- Flood Retention Only
  - 25-50% of bedload (4.3-8.7 acre-ft/yr)
- Larger amounts of woody debris expected during floods with 10-25 year recurrence interval
- 2007 flood event (extreme flood)
  - 2,000-3,000 acre-ft of coarse sediment
  - 230 acre-ft of woody debris

# Geomorphic Reaches and Sub-Reaches



# Geomorphic Reaches and Sub-Reaches



# Effects on Aquatic Habitat

## Reach 1 – Reservoir

Variable	Flood Retention Only	Multi-Purpose
Substrate/Spawning Gravel	Finer substrate/ transient delta	Inundated
Channel Width/Depth	Likely wider/ shallower wetted channel	Inundated
Large Woody Debris	Wood trapped – transported around dam	Wood trapped – transported around dam
Channel Migration	n/a - confined	n/a - confined

# Effects on Aquatic Habitat

## Confined Reaches – 2A, 2C, 4A, 4C

Variable	Flood Retention Only	Multi-Purpose
Substrate/Spawning Gravel	Minor changes	Erosion/ coarsening
Channel Width/Depth	Minor changes	Possible narrower channel
Large Woody Debris	Likely less LWD	Likely less LWD
Channel Migration	n/a - confined	n/a - confined

# Effects on Aquatic Habitat

## Unconfined Reaches – 2B, 3, 4B

Variable	Flood Retention Only	Multi-Purpose
Substrate/Spawning Gravel	2B - Continued aggradation/fining 3 - Minor changes 4B – Possible coarsening	Erosion/ coarsening
Channel Width/Depth	Minor changes	Possible narrower channel
Large Woody Debris	Likely less LWD	Likely less LWD
Channel Migration	Likely less channel migration	Likely less channel migration

# Effects on Aquatic Habitat

## Reaches 5, 6 – Downstream of RM 75

- Limited changes – bedrock control re-sets bedload transport
- Tributary input of water/wood sediment mute effects of flood control facilities

# Questions